

Lowest of Bids of Three

Res#
19-101



Trio Construction
455 Scioto Meadows Blvd
Grove City, OH 43123
(614)394-3417
criggs07@gmail.com

ESTIMATE

ADDRESS

Franklin Twp.
1963 Harrisburg pike Col Ohio

ESTIMATE # 1239

DATE 06/04/2019

ACTIVITY	QTY	RATE	AMOUNT
In the pump room , we will remove saturated and heavily molded materials and haul away.			
Treat mold in pump room.			
In remaining area of basement , scrape walls, remove loose debris and haul away.			
Treat mold in entire basement.			
We will then use concrobrum and apply as needed in entire basement .			
After remediation is complete we will seal joists and subflooring with mold x seal.			
We will then seal all walls using water tight sealer paint which will aid in keeping the walls dry.			
Although we wont be treating the upstairs I will apply concrobrum fogger to aid in containing any further mold growth.			
Services			
Clean and haul all job related debris.			8,238.00

Forms of payment: VISA, Mastercard, Half down to start. \$4,119.00
Balance due on completion.

TOTAL

\$8,238.00

Accepted By

Accepted Date

Accepted by: | Accepted Date: | Trio Construction Representative

Representative

| Accepted Date: | Trio Construction