## **Resolution 2025-062**

# Resolution Approving the Repair of Roofs for Township Buildings

The Board of Trustee of Franklin Township, Franklin County, Ohio met in person in a Regular Meeting at 12:00p.m. on Thursday May  $1^{\rm st}$ , 2025 . The Trustee marked below made a motion for the adoption of the following resolution:

made a motion for the adoption	on of the following resolution:	
☐ Trustee Fleshman	□ Trustee Leezer	☐ Trustee Blevins
<b>BE IT RESOLVED</b> that the Ohio that the Board approve Administrative Building and Exhibit)	es and authorizes roof and v	vall repairs to the Township
BE IT RESOLVED that all f Resolution were passed in an Board and any of its committe open to the public, in compliant the Ohio Revised Code	open meeting of the Board, ar tees that resulted in such for	nd that all deliberations of the mal action were in a meeting
BE IT FURTHER RESOLV	<b>ED</b> that this Resolution shall b	e declared an emergency and
be in full force and effective in The following trustee marked	nmediately upon its adoption. I below seconded the motion:	
□ Trustee Fleshman	☐Trustee Leezer	☐ Trustee Blevins
Roll was called for the adopti		
Fleshman: ☑ YES/ □NO	<b>Leezer:</b> ☑YES/ □NO	Blevins: ☐ YES/ ☑NO
	John Flesh	man, Chairman
	James Leez	er, Trustee
	Mike Blevin	BLs, Trustee
Attested to on this 1st Day of I	May 2025	
	And the state of t	



03/07/2025 BID-10958 #G05719 #HIC02450

ISPEC LLC PO BOX 163605 Columbus, OH 43216 1-614-725-0489

For any questions please contact:

Juhriah Smith 614-556-2238 juhriah@ispecllc.com

#### **Customer information:**

Steve Mazer
Franklin Township Administration Building
2193 Frank Rd.
Columbus, OH 43223
614-279-9411 (office) / 614-348-7026 (cell)
smazer@franklin-township.com

Job location: 2193 Frank Rd

#### **Estimate Request**

Contractor agrees to provide all equipment, materials and labor, unless otherwise noted.

Deisi

Remove water damaged drywall, carpet and framing. Replace with new.

### Drywall, Framing and Roofing

Remove approximately 8 lineal feet of T-111 wainscoting

Remove carpet, carpet pad and its tack strips

Remove water damaged drywall, approx. 6' x 8'

Remove insulation as necessary

Remove/cut out damaged metal framing, approx. 6 LF sill plate

Dust preparation-place plastic drop clothes over office items left in workspace

Install 6 lineal feet sill plate (metal channel)

Install approx. sister/double metal wall studs approx. 4-6 total

Install R-15 insulation where removed approx. 50 sq ft

Install type X fire rated drywall approx. up to 50 sq ft where removed, smooth sanded finish

Sillotti Salided Illiali

Install T-111 siding where removed

Cut off obsolete B-vent

Install metal plate over roof opening, seal patch with EPDM seam/edge tape

Remove all construction waste and debris from site

#### Painting

Paint all fresh drywall and drywall mud with a primer sealer

Paint room walls with Sherwin Williams Super paint, satin finish, color TBD

Paint wainscoting with Sherwin Williams Super paint, satin finish, color TBD

Flooring	
Install Shaw carpet tile, charcoal color, style: gradient, glue down	en e
	THE PARTY OF THE P

Wall construction	\$5,798.00
Painting	\$1,854.50
Flooring	\$1,869.50
Roof patch	\$420.00
Estimated Amount	\$9,942.00
**Adtl. Notes:	WOODTENDOO